


CROSS SECTION "A-A"  
SCALE: 1" = 5'

TEST HOLE DATA - September 5, 2019  
Northwest District Department of Health

TEST PIT	DEPTH	PROFILE
101	0" - 8" 8" - 19" 19" - 34" 34" - 68" 68"	Topsoil Red Brown Very Fine Sandy Loam Tan Fine Sandy Loam Gray Very Fine Sandy Loam Boney Ledge
102	0" - 8" 8" - 21" 21" - 38" 38" - 58" 58" - 92" 92"	Topsoil Red Brown Very Fine Sandy Loam Tan Fine Sandy Loam Gray Very Fine Sandy Loam Boney Dark Gray Tight Pan Ledge GW Mottling Restrictive

SEPTIC SYSTEM DESIGN DATA

- Percolation Rate = 6.7 min. / in.
  - 3 bedroom house requires = 485 s.f. effective leaching area
  - Effective Leaching area = 11 s.f. / l.f. of trench
  - Length Required = 485/11 = 45 l.f.
  - Length Provided = 45 l.f.
  - Min. Leaching System Spread (MLSS) = 18 x 1.50 x 1.0 = 27'
  - MLSS Provided = 45'
- LEACHING FIELD**
- 1 - 45' row (9 Sections) of Eljen Martie 536-8 septic leaching units
  - Maximum depth into existing grade = 18"




SURVEYOR SHALL SET A BENCH MARK IN THE AREA OF THE SEPTIC SYSTEM AT THE TIME OF CONSTRUCTION STAKE-OUT.

<b>SEPTIC TANK</b>	
1000 GALLON	
TWO COMPARTMENT	
F/L IN = 234.50	
F/L OUT = 234.25	
<b>DISTRIBUTION BOXES</b>	
D-1 (STANDARD)	
F/L IN = 233.67	
F/L OUT = 233.50	

n/f  
Pulcinella Family Revocable Living Trust  
Map 65, Lot 3  
(Undeveloped)

AREA = 1.92± ACRES  
(83,807 S.F.)



- LEGEND**
- F.F. FINISHED FLOOR
  - IRON PIN FOUND
  - CB CATCH BASIN
  - - - 100 - - - EXISTING CONTOURS
  - - - 100 - - - PROPOSED CONTOURS
  - WETLANDS FLAG INLAND WETLANDS FLAG
  - BUILDING SETBACK LINE
  - PERCOLATION TEST HOLE
  - TEST HOLE
  - - - SILT FENCE

APPROVED BY THE TOWN OF KILLINGLY INLAND WETLANDS COMMISSION

CHAIRMAN \_\_\_\_\_ DATE \_\_\_\_\_

ANY CHANGES TO THESE PLANS WITHIN 200' OF WETLANDS OR WATERCOURSES MUST BE RESUBMITTED TO THE KILLINGLY INLAND WETLANDS AND WATERCOURSES COMMISSION FOR ITS APPROVAL.

THE APPLICANT WILL CONTACT THE KILLINGLY INLAND WETLANDS AND WATERCOURSES COMMISSION'S AGENT AFTER ALL EROSION AND SEDIMENT CONTROL MEASURES ARE INSTALLED, PRIOR TO ANY CONSTRUCTION OR EXCAVATION ON THE PROPERTY.

I HAVE REVIEWED THE FLAGGED INLAND WETLANDS LOCATION SHOWN ON THIS PLAN AND THEY APPEAR TO BE SUBSTANTIALLY CORRECT.

Certified Soil Scientist \_\_\_\_\_ Date \_\_\_\_\_

NORMAND THIBEAULT, JR., P.E. No. 22834 DATE \_\_\_\_\_

**RECEIVED**  
DEC 01 2020  
PLANNING & ZONING DEPT.  
TOWN OF KILLINGLY

TO MY KNOWLEDGE AND BELIEF, THIS MAP IS SUBSTANTIALLY CORRECT AS NOTED HEREON,

GREG A. GLAUDE, L.S. LIC. NO. 70191 DATE \_\_\_\_\_

NO CERTIFICATION IS EXPRESSED OR IMPLIED UNLESS THIS MAP BEARS THE ORIGINAL SEAL AND SIGNATURE OF THE LAND SURVEYOR.

- NOTES:**
- This survey has been prepared pursuant to the Regulations of Connecticut State Agencies Sections 20-300b-1 through 20-300b-20 and the "Standards for Surveys and Maps in the State of Connecticut" as adopted by the Connecticut Association of Land Surveyors, Inc. on September 26, 1996; This map was prepared from record research, other maps, limited field measurements and other sources. It is not to be construed as a Property/Boundary or Limited Property /Boundary Survey and is subject to such facts as said surveys may disclose.
    - This survey conforms to a Class "C" horizontal accuracy.
    - Topographic features conform to a Class "T-2", "V-2" vertical accuracy.
    - Survey Type: General Location Survey.
  - Zone = RD.
  - Owner of record: Pulcinella Family Revocable Living Trust  
70 Seaview Avenue  
Branford, CT 06405
  - Parcel shown as Lot #7.1 on Assessors Map #65.
  - Elevations shown are based on an assumed datum. Contours shown are taken from actual field survey. Contour interval = 2'.
  - Test Pit data taken from NDDH file number 20G00044.
  - Wetlands shown were delineated in the field by Joseph Theroux, Certified Soil Scientist, in September 2019.
  - Before any construction is to commence contact "CALL BEFORE YOU DIG" at 1-800-922-4455 or 811.

**MAP REFERENCE:**

"Limited Property / Boundary Survey - First Lot Out (Free Split) Prepared for - Anthony & Josephine Pulcinella Family Revocable Trust - Breakneck Hill Road - Killingly, Connecticut - Scale: 1" = 80' - Date: September 2010 - Sheet No. 1 - Prepared by Archer Surveying, LLC." On file in the Killingly Land Records as Map #6430.

DATE	DESCRIPTION

GENERAL LOCATION SURVEY  
SEPTIC SYSTEM DESIGN PLAN  
PREPARED FOR  
**SEAN O'KEEFE**  
341 BREAKNECK HILL ROAD  
KILLINGLY, CONNECTICUT

**Killingly Engineering Associates**  
Civil Engineering & Surveying  
114 Westbrook Road  
P.O. Box 421  
Killingly, Connecticut 06241  
(860) 799-7299  
www.killinglyengineering.com

DATE: 10/22/2019	DRAWN: AMR
SCALE: 1" = 30'	DESIGN: NET
SHEET: 1 OF 2	CHK BY: GG
DWS No: CLIENT FILE	JOB No: 19114

**EROSION AND SEDIMENT CONTROL NARRATIVE:**

**PRINCIPLES OF EROSION AND SEDIMENT CONTROL**

The primary function of erosion and sediment controls is to absorb erosional energies and reduce runoff velocities that force the detachment and transport of soil and/or encourage the deposition of eroded soil particles before they reach any sensitive area.

**KEEP LAND DISTURBANCE TO A MINIMUM**

The more land that is in vegetative cover, the more surface water will infiltrate into the soil, thus minimizing stormwater runoff and potential erosion. Keeping land disturbance to a minimum not only involves minimizing the extent of exposure at any one time, but also the duration of exposure. Phasing, sequencing and construction scheduling are interrelated. Phasing divides a large project into distinct sections where construction work over a specific area occurs over distinct periods of time and each phase is not dependent upon a subsequent phase in order to be functional. A sequence is the order in which construction activities are to occur during any particular phase. A sequence should be developed on the premise of "first things first" and "last things last" with proper attention given to the inclusion of adequate erosion and sediment control measures. A construction schedule is a sequence with time lines applied to it and should address the potential overlap of actions in a sequence which may be in conflict with each other.

- Limit areas of clearing and grading. Protect natural vegetation from construction equipment with fencing, tree armoring, and retaining walls or tree wells.
- Route traffic patterns within the site to avoid existing or newly planted vegetation.
- Phase construction so that areas which are actively being developed at any one time are minimized and only that area under construction is exposed. Clear only those areas essential for construction.
- Sequence the construction of storm drainage systems so that they are operational as soon as possible during construction. Ensure all outlets are stable before outletting storm drainage flow into them.
- Schedule construction so that final grading and stabilization is completed as soon as possible.

**SLOW THE FLOW**

Detachment and transport of eroded soil must be kept to a minimum by absorbing and reducing the erosive energy of water. The erosive energy of water increases as the volume and velocity of runoff increases. The volume and velocity of runoff increases during development as a result of reduced infiltration rates caused by the removal of existing vegetation, removal of topsoil, compaction of soil and the construction of impervious surfaces.

- Use diversions, stone dikes, silt fences and similar measures to break flow lines and dissipate storm water energy.
- Avoid diverting one drainage system into another without calculating the potential for downstream flooding or erosion.

**KEEP CLEAN RUNOFF SEPARATED**

Clean runoff should be kept separated from sediment laden water and should not be directed over disturbed areas without additional controls. Additionally, prevent the mixing of clean off-site generated runoff with sediment laden runoff generated on-site until after adequate filtration of on-site waters has occurred.

- Segregate construction waters from clean water.
- Divert site runoff to keep it isolated from wetlands, watercourses and drainage ways that flow through or near the development until the sediment in that runoff is trapped or detained.

**REDUCE ON SITE POTENTIAL INTERNALLY AND INSTALL PERIMETER CONTROLS**

While it may seem less complicated to collect all waters to one point of discharge for treatment and just install a perimeter control, it can be more effective to apply internal controls to many small sub-drainage basins within the site. By reducing sediment loading from within the site, the chance of perimeter control failure and the potential off-site damage that it can cause is reduced. It is generally more expensive to correct off-site damage than it is to install proper internal controls.

- Control erosion and sedimentation in the smallest drainage area possible. It is easier to control erosion than to contend with sediment after it has been carried downstream and deposited in unwanted areas.
- Direct runoff from small disturbed areas to adjoining undisturbed vegetated areas to reduce the potential for concentrated flows and increase settlement and filtering of sediments.
- Concentrated runoff from development should be safely conveyed to stable outlets using rip rapped channels, waterways, diversions, storm drains or similar measures.
- Determine the need for sediment basins. Sediment basins are required on larger developments where major grading is planned and where it is impossible or impractical to control erosion at the source. Sediment basins are needed on large and small sites when sensitive areas such as wetlands, watercourses, and streams would be impacted by off-site sediment deposition. Do not locate sediment basins in wetlands or permanent or intermittent watercourses. Sediment basins should be located to intercept runoff prior to its entry into the wetland or watercourse.

**SEPTIC SYSTEM CONSTRUCTION NOTES**

1. The building, septic system and well shall be accurately staked in the field by a licensed Land Surveyor in the State of Connecticut, prior to construction.
2. Topsoil shall be removed and in the area of the primary leaching field certified, prior to placement of septic fill. Septic fill specifications are as follows:
  - Max. percent of gravel (material between No. 4 & 3 inch sieves) = 45%

GRADATION OF FILL (MINUS GRAVEL)

SIEVE SIZE	PERCENT PASSING (WET SIEVE)	PERCENT PASSING (DRY SIEVE)
No. 4	100%	100%
No. 10	70% - 100%	70% - 100%
No. 40	10% - 50%	10% - 75%
No. 100	0% - 20%	0% - 5%
No. 200	0% - 5%	0% - 2.5%

Fill material shall be approved by the sanitation prior to placement. It shall be compacted in 6" lifts and shall extend a minimum of five feet (5') around the perimeter of the system. Common fill shall extend an additional five feet (5') down gradient of the system (10' total) before tapering off at a maximum slope of 2H:1V.

3. Septic tank shall be two compartment precast 1000 gallon tank with gas deflector and outlet filter as manufactured by Jolley Precast, Inc. or equal.

4. Distribution boxes shall be 4 hole precast concrete as manufactured by Jolley Precast, Inc. or equal.

5. All precast structures such as septic tanks, distribution boxes, etc. shall be set level on six inches (6") of compacted gravel base at the elevations specified on the plans.

6. Solid distribution pipe shall be 4" diameter PVC meeting ASTM D-3034 SDR 35 with compression gasketed joints. It shall be laid true to the lines and grades shown on the plans and in no case shall have a slope less than 0.125 inches per foot.


7. Perforated distribution pipe shall be 4" diameter PVC meeting ASTM D-3034 or ASTM F1760 for SDR 35, or ASTM FB10 for SDR 38.

8. Sewer pipe from the foundation wall to the septic tank shall be schedule 40 PVC meeting ASTM D 1785. It shall be laid true to the grades shown on the plans and in no case shall have a slope less than 0.25 inches per foot.

9. Solid footing drain outlet pipe shall be 4" Diameter PVC meeting ASTM D 3034, SDR 35 with compression gasketed joints. Footing drain outlet pipe shall not be backfilled with free draining material, such as gravel, broken stone, rock fragments, etc.

10. Septic sand shall meet the requirements of ASTM C-33 with less than 10% passing a 100 sieve and less than 5% passing a 200 sieve


SIEVE SIZE	% PASSING
0.375	100
#4	85-100
#8	80-100
#16	80-85
#30	25-80
#50	10-30
#100	<10
#200	<5




NOTE: CONTRACTOR SHALL PROVIDE SILT/CLAY DAMS AT 100' INTERVALS ALONG PROPOSED UTILITY TRENCH TO AVOID TRANSPORTING INTERCEPTED WATER.

**UNDERGROUND UTILITY TRENCH**


NOT TO SCALE



PLAN VIEW



LAND ABOVE ROAD (SECTION)




LAND BELOW ROAD (SECTION)

1. THE ABOVE DETAIL IS ILLUSTRATIVE ONLY AND DOES NOT APPLY TO EVERY SITUATION. REVIEW YOUR DRAINAGE PLAN FOR YOUR SPECIFIC REQUIREMENTS.
2. DRIVEWAYS IN EXCESS OF 10% GRADE, AND ALL COMMON (SHARED) DRIVEWAYS SHALL BE PAVED WITH BITUMINOUS CONCRETE.


**STANDARD DRIVE DETAIL**

NOT TO SCALE




**SILT FENCE**

NOT TO SCALE




**ANTI-TRACKING PAD**

NOT TO SCALE





PLAN



CROSS SECTION


**1000 GALLON 2 COMPARTMENT SEPTIC TANK**

NOT TO SCALE




- NOTES:
1. VENTING REQUIRED WHEN MORE THAN 18" OF COVER IS MEASURED FROM THE TOP OF THE UNIT TO FINISHED GRADE.
  2. FOR SYSTEMS INSTALLED IN FILL, CONTRACTOR SHALL PROVIDE 5" OF SELECT FILL OR ASTM C-33 SAND 5' AROUND PERIMETER OF SYSTEM.

**ELJEN 536-8 WASTEWATER LEACHING SYSTEM**



**MODIFIED RIPRAP SWALE**

NOT TO SCALE



**STANDARD D-BOX**

NOT TO SCALE

DATE	DESCRIPTION

DETAIL SHEET  
PREPARED FOR  
**SEAN O'KEEFE**

341 BREAKNECK HILL ROAD  
KILLINGLY, CONNECTICUT

**Killingly Engineering Associates**  
Civil Engineering & Surveying  
114 Westport Road  
P.O. Box 421  
Killingly, Connecticut 06241  
(860) 779-7299  
www.killinglyengineering.com

DATE: 10/22/2019	DRAWN: AMR
SCALE: NOT TO SCALE	DESIGN: NET
SHEET: 2 OF 2	CHK BY: GG
DWG. No: CLIENT FILE	JOB No: 19114

NORMAN THIBEAULT, JR., P.E. No. 22834 DATE

PLANNING & ZONING DEPT.  
TOWN OF KILLINGLY

DEC 01 2020

**RECEIVED**