

 $\mathbf{\Omega}$ 9 0  $\Delta$ posal repai  $\propto$ 

S

1" = 20'

December 2021

21-3089


Revisions Rev. "A" - Per Town Eng

Comments - 2/7/22

SHEET NO.


# **MANTIS 536-8: CROSS SECTION**

**NOT TO SCALE** 




### CONCRETE SEPTIC TANK DETAIL

NOT TO SCALE




## CONCRETE PUMP CHAMBER DETAIL

NOT TO SCALE




NOT TO SCALE




#### **BITUMINOUS CONCRETE PAVEMENT** NOT TO SCALE

-4" ROLLED BANK RUN GRAVEL CONFORMING TO CT DOT FORM 816 M.O2.O3 AND M.02.06 GRADATION "C" OR COMPACTED 1-1/4" PROCESSED TRAPROCK MIX




## TRAFFIC BOUND GRAVEL SURFACE


NOT TO SCALE



#### **ANTI-TRACKING PAD** NOT TO SCALE



#### SEDIMENT FENCE DETAIL NOT TO SCALE



#### KILLINGLY STANDARD DRIVEWAY DETAIL **NOT TO SCALE**

2. DRIVEWAYS IN EXCESS OF 10% GRADE,

AND ALL COMMON ( SHARED ) DRIVEWAYS SHALL BE PAVED WITH BITUMINOUS

CONCRETE.

**NARRATIVE** 

THIS PROPOSAL INVOLVES THE REDEVELOPMENT OF AN EXISTING 7.10± ACRE PROPERTY LOCATED AT 146 PINEVILLE ROAD IN THE TOWN OF KILLINGLY, CONNECTICUT, THE PROPERTY CURRENTLY CONTAINS AN EXISTING AGRICULTURAL BARN AND GRAVEL DRIVEWAY AND IS INTENDED TO BE REDEVELOPED FOR RESIDENTIAL USE. THE CURRENT ZONING DESIGNATION OF THE SUBJECT PROPERTY IS RURAL DEVELOPMENT (RD)

IMPROVEMENTS TO THE SITE REQUIRED TO SUPPORT THE PROPOSED RESIDENTIAL USE INCLUDES: DEMOLITION OF THE EXISTING BARN AND CONSTRUCTION OF A NEW TWO-BEDROOM SINGLE-FAMILY RESIDENCE IN THE FORMER BARN'S LOCATION; CONSTRUCTION OF A DETACHED GARAGE WITH 900 SF ACCESSORY DWELLING UNIT; A NEW DRIVEWAY TO ACCESS THE RESIDENCE AND GARAGE; A CODE COMPLIANT SUBSURFACE SEWAGE DISPOSAL SYSTEM (SSDS); DRILLED WATER SUPPLY WELL; ASSOCIATED SITE GRADING, AND EROSION & SEDIMENT

ACCORDING TO THE UNITED STATES DEPARTMENT OF AGRICULTURE (USDA), NATURAL RESOURCES CONSERVATION SERVICE (NRCS) WEB SOIL SURVEY FOR THE STATE OF CONNECTICUT, THE SOILS LOCATED UPON THE SUBJECT PROPERTY WITHIN THE AREA OF PROPOSED DEVELOPMENT

38C HINCKLEY LOAMY SAND, 3-15% SLOPES 701A NINIGRET FINE SANDY LOAM, 0-3% SLOPES

INLAND WETLANDS DEPICTED ON THIS PLAN WERE DELINEATED BY DEMIAN SORRENTINO, C.S.S. THE PROPOSAL INCLUDES THE FILLING OF A 630 SF ISOLATED WETLAND AREA THAT HAS FORMED IN WHAT IS LIKELY AN OLD EXCAVATED AREA OR BURY PIT. NO DISTURBANCE OF THE LARGER RIPARIAN WETLANDS ASSOCIATED WITH THE FIVE MILE RIVER IS PROPOSED BY THIS PLAN. LAND DISTURBING ACTIVITY IS PROPOSED WITHIN THE 100' UPLAND REVIEW AREA, WHICH WILL REQUIRE ISSUANCE OF A PERMIT TO CONDUCT REGULATED ACTIVITY FROM THE KILLINGLY INLAND WETLANDS & WATERCOURSES COMMISSION.

TOPSOIL SHALL BE STOCKPILED ON SITE FOR REUSE IN CONJUNCTION WITH FINAL GRADING AND FOR FINAL SITE STABILIZATION AFTER GRADING IS COMPLETED, A 4" MINIMUM DEPTH OF TOPSOIL SHALL BE PLACED AND SEEDED WITH GRASS AND MULCHED WITH HAY OR STRAW FOR PERMANENT STABILIZATION.

SEDIMENT FENCE OR WOOD CHIP BERMS SHALL BE INSTALLED AT LOCATIONS SHOWN PRIOR TO ANY EARTHWORK OPERATIONS. THESE MEASURES WILL BE MAINTAINED UNTIL ALL DISTURBED AREAS HAVE BEEN PERMANENTLY STABILIZED.


#### **SANITARY NOTES**

- 1. THIS SEPTIC SYSTEM INSTALLATION INCLUDING ALL MATERIALS (PIPING, SEPTIC TANK, STONE, FILL, ETC.) USED FOR THIS SEPTIC SYSTEM SHALL CONFORM TO THE CURRENT EDITION/REVISION OF THE "TECHNICAL STANDARDS FOR SUBSURFACE SEWAGE DISPOSAL SYSTEMS" REVISED JANUARY 1, 2018 OF THE CONNECTICUT PUBLIC HEALTH CODE BY THE STATE OF CONNECTICUT DEPARTMENT OF PUBLIC HEALTH.
- 2. THE PROPOSED HOUSE SEWER FROM THE BUILDING TO THE SEPTIC TANK SHALL BE SCHEDULE 40 PVC ASTM D 1785/ASTM D 2665 OR APPROVED EQUAL AND INDICATED IN TABLE NO. 2 OF "TECHNICAL STANDARDS FOR SUBSURFACE SEWAGE DISPOSAL SYSTEMS". ALL OTHER SEWER PIPE FOR THIS SEPTIC SYSTEM SHALL BE 4" PVC ASTM D3034, SDR 35 WITH RUBBER COMPRESSION GASKET OR BELL AND SPIGOT OR APPROVED EQUAL.
- 3. THERE ARE NO WELLS (POTABLE, GEOTHERMAL, OR IRRIGATION) WITHIN 75' OF THE PROPOSED SEPTIC SYSTEM. THERE ARE NO SEPTIC SYSTEMS WITHIN 75' OF THE PROPOSED WELL.
- 4. THERE SHALL BE NO STUMPS BURIED ON SITE OR BOULDERS BURIED WITHIN 50' DOWN GRADIENT OF THE SEPTIC SYSTEM. SHOULD ANY SIGNIFICANT VARIATIONS FROM THE TEST HOLE DATA BE ENCOUNTERED DURING EXCAVATIONS (LEDGE, GROUNDWATER, MOTTLING, SOIL TYPE, ETC.), THE DESIGN ENGINEER SHALL BE NOTIFIED PRIOR TO INSTALLATION OF THE SEPTIC SYSTEM. 5. ALL EXISTING UTILITIES ARÉ APPROXIMATE ONLY. THE CONTRACTOR SHALL VERIFY ALL UTILITY LOCATIONS AND ELEVATIONS PRIOR TO ANY CONSTRUCTION. CONTRACTOR SHALL CONTACT "CALL-BEFORE-YOU-DIG" AT 1-800-922-4455 AT LEAST 72 HOURS PRIOR TO ANY EXCAVATION.
- 6. THE PROPOSED FILL FOR THIS SEPTIC SYSTEM SHALL MEET THE FOLLOWING SPECIFICATIONS: A. 100% OF FILL SHALL PASS THROUGH A 3" SIEVE.

B. MAXIMUM % OF GRAVEL (BETWEEN #4 & 3" SIEVE) = 45% C. GRADATION OF FILL WITHOUT THE GRAVEL SHALL MEET THE FOLLOWING CRITERIA: <u>% PASSING (WET)</u> <u>% PASSING (DRY)</u> 100%

70 – 100% 70 - 100% 10 - 50%\* 10 - 75% 0 - 20% 0 - 5% 0 - 5% 0 - 2.5% D. \* PERCENT PASSING THE #40 WET SIEVE CAN BE INCREASED TO NO GREATER THAN 75% IF THE PERCENT PASSING THE

- #100 SIEVE DOES NOT EXCEED 10% AND THE #200 SIEVE DOES NOT EXCEED 5%. PERCOLATION RATE AFTER PLACEMENT AND COMPACTION SHALL BE FASTER THAN OR EQUAL TO 10.0 MINUTES/INCH. A WET OR DRY SIEVE ANALYSIS MAY BE REQUIRED PRIOR TO FILL PLACEMENT TO VERIFY THAT IT MEETS THESE SPECIFICATIONS. THE FILL SHALL BE APPROVED BY THE LOCAL HEALTH DISTRICT/DEPARTMENT OR DESIGN ENGINEER PRIOR TO ITS PLACEMENT
- ELJEN MANTIS SPECIFIED SAND SHALL CONFORM TO ASTM C33 SAND WITH LESS THAN 10% PASSING #100 SIEVE AND LESS THAN 5% PASSING #200 SIEVE BASED ON A WET SIEVE ANALYSIS. 8. NO DEVIATION FROM THE APPROVED DESIGN PLAN SHALL BE ALLOWED WITHOUT PRIOR WRITTEN APPROVAL FROM THE LOCAL
- HEALTH DISTRICT/DEPARTMENT AND THE DESIGN ENGINEER. 9. THE SEPTIC TANK AND PUMP CHAMBER SHALL BE PRECAST CONCRETE UNLESS OTHERWISE AUTHORIZED BY THE DESIGN ENGINEER. THE TANK SHALL BE TESTED WATERTIGHT AS VERIFIED BY THE LOCAL HEALTH DEPARTMENT/DISTRICT (VACUUM TEST OR WATER PRESSURE TEST) IN ACCORDANCE WITH SECTION V.A.6. OF THE TECHNICAL STANDARDS. IF RISER ASSEMBLIES ARE UTILIZED OVER CLEANOUT OPENINGS, THE COVERS SHALL BE LEFT ON THE TANK. RISER COVERS SHALL WEIGH AT LEAST 59 POUNDS AND A SECONDARY SAFETY LID OR DEVICE SHALL BE PROVIDED INSIDE THE RISER.
- THIS SEPTIC SYSTEM HAS NOT BEEN SIZED TO INCLUDE CAPACITY FOR A GARBAGE GRINDER OR LARGE TUB. A GARBAGE GRINDER OR LARGE TUB SHALL NOT BE USED IN THE RESIDENCE WITHOUT INCREASING THE SIZE OF THE SEPTIC TANK. IF A GARBAGE GRINDER OR LARGE TUB IS DESIRED THEN THE SEPTIC TANK SIZE SHALL BE INCREASED IN ACCORDANCE WITH SECTION V.B.4 OF THE TECHNICAL STANDARDS. WATER TREATMENT WASTEWATER (WATER SOFTENER) SHALL NOT BE DISCHARGED TO THIS SEPTIC SYSTEM.
- . THE SUBMERSIBLE EFFLUENT PUMP SHALL BE A LIBERTY PUMPS MODEL FL-31, 115 VOLT, SINGLE PHASE, 1/3 HP, 1,725 RPM OR APPROVED EQUAL CAPABLE OF PUMPING 28 GPM WITH A TOTAL DYNAMIC HEAD OF 15 FEET. EACH PUMP CYCLE SHALL DISCHARGE 110± GALLONS. THE PUMP SHALL BE INSTALLED IN A 1,000 GALLON (MINIMUM) PRECAST CONCRETE PUMP CHAMBER WITH A CHECK VALVE AND DISCONNECT INSTALLED ON THE FORCE MAIN BENEATH THE MANHOLE RISER AT A DEPTH NOT GREATER THAN 30" BELOW ACCESS GRADE. A WEEP HOLE SHALL BE INSTALLED IN THE FORCE MAIN JUST UPSTREAM OF THE CHECK VALVE TO ALLOW PIPE TO DRAIN WHEN PUMP IS OFF. PUMP SHALL BE EQUIPPED WITH A VISIBLE AND AUDIBLE HIGH LEVEL ALARM. AN ELECTRICAL PERMIT IS REQUIRED FROM THE TOWN BUILDING OFFICIAL
- 12. THE PROPOSED SANITARY FORCE MAIN SHALL BE 2" SCHEDULE 40 PVC PRESSURE PIPE (ASTM D 1785) OR APPROVED EQUAL AND INDICATED IN TABLE NO. 2-B OF THE TECHNICAL STANDARDS. THIS PIPE SHALL BE PITCHED TO DRAIN BACK TO THE PUMP CHAMBER OR BE INSTALLED WITH A MINIMUM OF 42" OF COVER WHEREVER POSSIBLE. 13. SITE PREPARATION PROCEDURE FOR THE INSTALLATION OF THE PROPOSED SEPTIC SYSTEM:
- A. STRIP ALL TOPSOIL, VEGETATION AND ORGANIC MATERIAL IN THE AREA OF, AND 5' SURROUNDING, THE PRIMARY LEACHING TRENCHES EXTENDING TO THE LIMITS SHOWN ON CROSS SECTION A-A. B. USING A HEAVY RAKE OR EQUAL, THOROUGHLY SCARIFY AND ROUGHEN UP THE EXPOSED SOIL. REMOVE ANY LARGE STONES (3"+) AND OTHER DEBRIS. PREVENT ANY VEHICULAR TRAFFIC, BACKHOE, TRUCKS, ETC. FROM SMOOTHING/COMPACTING THE
- C. PLACE AND COMPACT SELECT FILL MATERIAL MEETING SPECIFICATIONS INDICATED ABOVE (NOTE #6) IN LIFTS OF NOT GREATER THAN 12" IN THE AREA OF THE PROPOSED LEACHING SYSTEM UP TO AT LEAST THE ELEVATION OF THE TOP OF THE LEACHING SYSTEM. SELECT FILL SHALL BE PLACED 5' FROM THE EDGE OF THE SYSTEM AND SLOPE TO THE EXISTING SUBSOIL AT 2H:1V D. PERFORM AT LEAST 1 PERCOLATION TEST ON PLACED FILL. FILL MUST HAVE A PERCOLATION RATE EQUAL TO OR FASTER THAN
- THAT AS INDICATED IN NOTE #6E. IF PERCOLATION RATE IS SLOWER THAN THAT RATE, ALL FILL SHALL BE REMOVED AND REPLACED WITH ACCEPTABLE FILL MEETING PROPER SPECIFICATIONS. E. EXCAVATE TRENCH TO DESIGN GRADES AND INSTALL SEPTIC SYSTEM PER MANUFACTURER'S SPECIFICATIONS (SEE WWW.ELJEN.COM
- OR CONTACT 1-800-444-1359) AS SHOWN ON THIS PLAN USING APPROVED MATERIALS (SAND, PIPE, ETC.). NOTE: THE MANTIS UNITS ARE NOT APPROVED FOR AND SHALL NOT BE INSTALLED UNDER TRAVELLED/PARKING AREAS. F. AFTER SETTLING. THE COVER OVER THE SYSTEM SHALL BE A MINIMUM OF 6" AND A MAXIMUM OF 18" OF MATERIAL MEASURED
- FROM THE TOP OF THE MODULE TO FINISHED GRADE. GRADE TO PREVENT PONDING AND SEED WITH GRASS TO STABILIZE. THE FINISHED GRADE 10' FROM ANY PART OF THE PROPOSED MANTIS UNITS SHALL BE AT LEAST THE SAME ELEVATION AS THE TOP OF THE MANTIS UNITS. DO NOT DRIVE OR PAVE OVER SYSTEM. G. ACCESS MANHOLES AT THE INLET BAFFLE AND AT THE OUTLET FILTER OF THE SEPTIC TANK SHALL BE INSTALLED TO WITHIN 12" OF FINISHED GRADE.
- 12. FOR EXACT HOUSE DIMENSIONS, SEE BUILDING PLANS. 13. BENCHMARK SHALL BE LOCATED IN THE AREA OF DEVELOPMENT PRIOR TO THE START OF CONSTRUCTION. 14. PRIOR TO CONSTRUCTION, THE BUILDINGS, WELL AND SEPTIC SYSTEM SHALL BE STAKED OUT BY A LICENSED LAND SURVEYOR.



#### PIPE AND OUTLET PROTECTION DETAIL

# **OPERATION & MAINTENANCE OF EROSION**

NO CONSTRUCTION SHALL PROCEED UNTIL PROPER SEDIMENTATION AND EROSION CONTROL MEASURES HAVE BEEN INSTALLED AS THE SEQUENCE OF CONSTRUCTION NECESSITATES.

ALL TEMPORARY FILL, STORAGE OR STOCKPILE AREAS SHALL BE PROPERLY STABILIZED TO PREVENT EROSION AND SUITABLY CONTAINED TO PREVENT TURBID RUNOFF. ALL AREAS AFFECTED BY TEMPORARY FILLS MUST BE RESTORED TO THEIR ORIGINAL CONTOURS AND REVEGETATED WITH SUITABLE VEGETATION. THE USE OF TEMPORARY FILL AND/OR EXCAVATION SHALL BE MINIMIZED TO ONLY THAT AREA REQUIRED TO PERFORM THE WORK.

DUMPING OF OIL OR OTHER DELETERIOUS MATERIALS ON THE GROUND IS FORBIDDEN. THE DEVELOPER OR CONTRACTOR SHALL PROVIDE A MEANS OF CATCHING, RETAINING AND PROPERLY DISPOSING OF DRAINED OIL. REMOVED OIL FILTERS. OR OTHER DELETERIOUS MATERIAL FROM EQUIPMENT USED ON SITE. VEHICLE MAINTENANCE SHALL BE COMPLETED OFF SITE. ALL OIL SPILLS SHALL BE IMMEDIATELY REPORTED TO THE DEPARTMENT OF ENERGY AND ENVIRONMENTAL PROTECTION/HAZARDOUS MATERIALS OFFICE. FAILURE TO DO SO MAY RESULT IN THE IMPOSITION OF FINES UNDER THE APPLICABLE CONNECTICUT GENERAL STATUTES.

EVERY PRECAUTION SHALL BE TAKEN DURING CONSTRUCTION TO PREVENT AND MINIMIZE THE DEGRADATION OF THE EXISTING WATER QUALITY. ALL ACTIVITIES SHALL BE IN CONFORMANCE TO AND CONSISTENT WITH ALL APPLICABLE WATER QUALITY STANDARDS AND MANAGEMENT PRACTICES AS SET FORTH BY LOCAL, STATE AND FEDERAL AGENCIES.

DURING THE PERIOD OF CONSTRUCTION, THE CONTRACTOR IS RESPONSIBLE FOR ALL EROSION AND SEDIMENT CONTROL MEASURES. SAID MEASURES SHALL BE INSPECTED WEEKLY AND AFTER EACH RAINSTORM. ACCUMULATED DEPOSITS OF SEDIMENT AND SILT SHALL BE PERIODICALLY REMOVED FROM THE UPSTREAM SIDE OF THE EROSION AND SEDIMENT CONTROL BARRIERS, AND UPON ESTABLISHMENT OF PERMANENT VEGETATIVE COVER. SUCH MATERIALS REMOVED SHALL BE SPREAD AND STABILIZED IN NON-WETLAND AREAS WHICH ARE NOT SUBJECT TO EROSION, OR WHICH ARE NOT TO BE PAVED OR

WOOD CHIP BERMS, SEDIMENT FENCE AND OTHER EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REPAIRED. CLEANED AND/OR REPLACED AS NECESSARY THROUGHOUT THE CONSTRUCTION PERIOD IN ORDER TO MAINTAIN COMPLETE AND INTEGRAL EROSION AND SEDIMENT CONTROL PROTECTION. ONCE IN PLACE, ALL EROSION AND SEDIMENT CONTROL FACILITIES AND MEASURES ARE TO REMAIN IN PLACE AND IN PROPER CONDITION AND BE CONTINUOUSLY MAINTAINED UNTIL FINAL GRADING HAS BEEN COMPLETED. ALL DISTURBED AREAS UPGRADIENT OF SAID FACILITIES HAVE BEEN PERMANENTLY STABILIZED AND ALL NEWLY GRASSED AREAS HAVE HAD AT LEAST TWO MOWINGS FOLLOWING SLICH PERMANENT STABILIZATION, THE FACILITIES SHALL BE DISMANTLED, REMOVED, AND DISPOSED OF IN AN APPROVED MANNER. ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES BEYOND THOSE SHOWN ON THE PLANS OR PRESCRIBED HEREIN SHALL BE PUT IN PLACE, WHENEVER NECESSARY, TO ADDRESS FIELD CONDITIONS AND/OR AS ORDERED BY THE TOWN STAFF OR THEIR DESIGNATED AGENT.

DISTURBANCE OF THE LAND SHALL BE LIMITED TO THE MINIMUM EXTENT NECESSARY TO COMPLETE THE PROPOSED DEVELOPMENT. ALL EXISTING TREES AND SHRUBS SHALL BE CONSERVED WHERE POSSIBLE EXCEPT THOSE WHOSE REMOVAL IS REQUIRED TO PERFORM THE PROPOSED WORK. THE LIMITS OF DISTURBANCE SHALL BE ESTABLISHED IN THE FIELD PRIOR TO STARTING ANY ACTUAL CONSTRUCTION ACTIVITIES AND SHALL BE GENERALLY AS DEPICTED ON THIS PLAN.

THE CONTRACTOR SHALL BE RESPONSIBLE FOR INSPECTING THE SITE IN ACCORDANCE WITH THE PROCEDURES AS OUTLINED IN THE "GENERAL PERMIT FOR THE DISCHARGE OF STORMWATER AND DEWATERING WASTEWATERS FROM CONSTRUCTION ACTIVITIES" AS ADOPTED BY THE DEPARTMENT OF ENERGY AND ENVIRONMENTAL PROTECTION, EFFECTIVE ON DECEMBER 31, 2020.

THE CONTRACTOR SHALL INSPECT ALL DISTURBED AREAS OF CONSTRUCTION ACTIVITY THAT HAVE NOT BEEN FINALLY STABILIZED, STRUCTURAL CONTROL MEASURES, AND LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE AT LEAST ONCE EVERY SEVEN CALENDAR DAYS AND WITHIN 24 HOURS OF THE END OF ALL RAIN EVENTS. WHERE SITES HAVE BEEN TEMPORARILY OR FINALLY STABILIZED, SUCH INSPECTION SHALL BE CONDUCTED AT LEAST ONCE EVERY MONTH FOR THREE CONSECUTIVE MONTHS.

DURING CONSTRUCTION AND IMMEDIATELY FOLLOWING CONSTRUCTION, THE CONTRACTOR SHALL BE RESPONSIBLE FOR SITE INSPECTION AND MAINTENANCE TO ASSURE PROPER PERFORMANCE OF THE SEDIMENTATION AND EROSION CONTROL SYSTEM. INSPECTING AND MAINTAINING SHALL INCLUDE, AT A MINIMUM, THE FOLLOWING: \* INSPECTION OF ALL SEDIMENT FENCE AND STAKED HAY BALES, REMOVE ACCUMULATED SEDIMENT

- IF REQUIRED (GREATER THAN 4" DEPTH) \* INSPECTION OF ANTI-TRACKING PAD, RÉMOVE, DISPOSE AND REPLACE IF PAD IS NO LONGER FUNCTIONAL IN THE CATCHMENT OF SEDIMENTS FROM VEHICULAR/TRUCK TRAFFIC.
- \* INSPECTION OF ALL DRIVEWAY AND PARKING AREAS AFTER PAVING, REMOVE ACCUMULATED SEDIMENT AND ANY LITTER/DEBRIS.

DISTURBED AREAS AND AREAS USED FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO PRECIPITATION SHALL BE INSPECTED FOR EVIDENCE OF, OR THE POTENTIAL FOR, POLLUTANTS ENTERING THE DRAINAGE SYSTEM. EROSION AND SEDIMENT CONTROL MEASURES IDENTIFIED IN THE PLAN SHALL BE INSPECTED TO INSURE THAT THEY ARE OPERATING CORRECTLY. DISCHARGE LOCATIONS OR POINTS SHALL BE INSPECTED TO ASCERTAIN WHETHER EROSION CONTROL MEASURES ARE EFFECTIVE IN PREVENTING SIGNIFICANT IMPACTS TO DOWNSTREAM WATERS. LOCATIONS WHERE VEHICLES ENTER OR EXIT THE SITE SHALL BE INSPECTED FOR EVIDENCE OF OFF-SITE SEDIMENT TRACKING.

THE CONTRACTOR SHALL APPOINT AN AGENT WHO SHALL BE PERSONALLY RESPONSIBLE FOR IMPLEMENTING THIS EROSION AND SEDIMENT CONTROL PLAN AND ENFORCING THE PRESCRIBED SAFEGUARDS DURING THE CONSTRUCTION PERIOD.

THIS RESPONSIBILITY INCLUDES THE INSTALLATION AND MAINTENANCE OF CONTROL MEASURES THROUGHOUT THE CONSTRUCTION PERIOD. INFORMING ALL PARTIES ENGAGED ON THE CONSTRUCTION SITE OF THE REQUIREMENTS AND OBJECTIVES OF THE PLAN. NOTIFYING THE PROPER TOWN AGENCIES AND OFFICIALS OF ANY TRANSFER OF THIS RESPONSIBILITY. AND CONVEYING A COPY OF THE APPROVED EROSION AND SEDIMENT CONTROL PLAN IF THE TITLE OF THE LAND IS TRANSFERRED TO A

#### **EROSION CONTROL NOTES**

- 1. ALL UTILITIES ARE APPROXIMATE. CONTRACTOR TO VERIFY ALL UTILITIES PRIOR TO CONSTRUCTION. CONTACT "CALL-BEFORE-YOU-DIG" AT 1-800-922-4455 AT LEAST 72 HOURS PRIOR TO ANY
- 2. THE RESPONSIBLE PARTY FOR THE INSTALLATION AND MAINTENANCE OF ALL EROSION CONTROL MEASURES IS THE SITE CONTRACTOR.
- 3. THE "2002 CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL" BY THE CONNECTICUT COUNCIL ON SOIL AND WATER CONSERVATION IN COOPERATION WITH THE CONNECTICUT DEPARTMENT OF ENVIRONMENTAL PROTECTION, CT DEEP BULLETIN 34, SHALL BE USED FOR INSTALLING AND MAINTAINING ALL EROSION CONTROL MEASURES. THE PROPERTY OWNER SHALL INSTALL ADDITIONAL MEASURES AS NECESSARY IF DIRECTED BY THE ENGINEER OR TOWN
- 4. SEEDING FOR PERMANENT STABILIZATION SHALL BE COMPLETED BETWEEN APRIL 15 THROUGH JUNE 15 OR BETWEEN AUGUST 15 THROUGH SEPTEMBER 15. IF SEEDING CANNOT BE COMPLETED WITHIN THESE TIMES, APPLICATION OF TEMPORARY MULCH WILL BE CONDUCTED UNTIL THE NEXT SEEDING PERIOD. SEED MIXTURE SHALL BE AS FOLLOWS: KENTUCKY BLUEGRASS 20 LBS/ACRE OR 0.45 LBS/1.000 S.F. CREEPING RED FESCUE 20 LBS/ACRE OR 0.45 LBS/1,000 S.F.
- PERENNIAL RYEGRASS 5 LBS/ACRE OR 0.10 LBS/1,000 S.F. 5. MULCH SHALL BE A GOOD QUALITY HAY OR STRAW AND SHALL BE APPLIED AT A RATE OF APPROXIMATELY 2-3 BALES/1,000 SF.
- ALL EROSION CONTROL MEASURES SHALL BE INSPECTED WITHIN 24 HOURS AFTER RAIN EVENTS WITH GREATER THAN 0.5" OF RAINFALL IN A 24-HOUR PERIOD, AND REPAIRED OR REPLACED AS NECESSARY TO INSURE COMPLIANCE WITH THE APPROVED SOIL EROSION AND SEDIMENT CONTROL

#### **CONSTRUCTION SEQUENCE**

- SECURE ALL NECESSARY LOCAL, STATE AND FEDERAL PERMITS. 2. INSTALL SEDIMENT FENCE IN SPECIFIED LOCATIONS AS SHOWN DOWNGRADIENT OF PROPOSED DEVELOPMENT AREA AND INSTALL ANTI-TRACKING PAD AT CONSTRUCTION ENTRANCE. STRIP TOPSOIL FROM DEVELOPMENT AREA AND STOCKPILE AT AN APPROVED LOCATION FOR LATER REUSE. SEED TOPSOIL STOCKPILE WITH RYEGRASS FOR TEMPORARY STABILIZATION. 3. DEMOLISH EXISTING BARN AND RETAINING WALLS. DISPOSE OF ALL DISCARDED MATERIALS AT AN
- APPROVED, OFF-SITE LOCATION. 4. EXCAVATE FOR BUILDING FOUNDATIONS. INSTALL BUILDING FOUNDATIONS.
- 5. PERFORM ALL NECESSARY ROUGH GRADING FOR BUILDING AND SUBSURFACE SEWAGE DISPOSAL
- 6. INSTALL UTILITY CONDUIT. CONSTRUCT HOUSE. INSTALL SUBSURFACE SEWAGE DISPOSAL SYSTEM AND WATER SUPPLY WELL. PERFORM FINAL SITE GRADING.
- 7. AT COMPLETION OF CONSTRUCTION, LOAM ALL DISTURBED AREAS (4" MINIMUM), SEED WITH GRASS AND MULCH. AFTER ALL AREAS HAVE BEEN PERMANENTLY STABILIZED, REMOVÉ EROSION CONTROL

SHEET NO.

As Noted

December 2021

Revisions

Rev. "A" - Per Town Eng

Comments - 2/7/22

21-3089

S

Q

0

Q

0

C

0

mp

ധ

0

0

 $\mathbf{\Omega}$ 

 $\boldsymbol{\sigma}$ 

a)

2

0

 $\propto$ 

 $\propto$ 

THIS DRAWING IS THE PROPERTY OF BOUNDARIES LLC AND HAS BEEN SPECIFICALLY PREPARED FOR THE OWNER OF THIS PROJECT, AT THIS SITE, AND IS NOT TO BE DUPLICATED OR USED IN PART OR WHOLE FOR ANY OTHER PURPOSE, PROJECT, LOCATION OR OWNER WITHOUT THE EXPRESSED WRITTEN CONSENT OF BOUNDARIES LLC.

**NOT TO SCALE** 

-PROPERTY LINE OR

LAND BELOW ROAD